



Club at Norwich Inn - Phase 1b Additional Work Order #1 (As Requested)
1988 Old Pond Lane, Norwich, CT 06360

Item
1.0

Replace Add'l Portion of Existing Concrete Patio with Pavers at Clubhouse #2 Approx 100 sq ft

- Sawcut, Remove and Dispose Existing Concrete Patio
- Excavate 4" and Compact Subgrade
- Install Processed Aggregate Base and Sand Bedding
- Furnish and Install New Pavers
- Install Polymeric Jointing Sand
- Misc Items, Engineering Layout, and Site Clean-up

Notes:

1. Limits of patio removal to be verified prior to start of work
2. Estimate based on Blu-60 pavers by Techo-Bloc
3. All excavation and compaction per industry standards
4. 5"-6" of processed aggregate base req'd
5. 1" sand layer to be placed under pavers
6. Jointing sand shall be Polymeric Sand or Equivalent
7. Existing concrete patio varies between 5" - 6" thick

Sub Total	\$	3,565.64
Tax	\$	226.42
Total	\$	3,792.06

Item
2.0

Add'l Work Required to Remove Thicker Concrete Patio at Clubhouse #2

- Add'l Labor Required to Sawcut and Remove Panels
- Add'l Costs to Rent Larger Concrete Saw
- Add'l Costs to Rent Jackhammer
- Add'l Excavation to Remove Soft Sand
- Add'l Processed Gravel to Strengthen Base Course

Notes:

1. Original work scope estimated concrete thickness as 4"
2. Existing concrete patio varies between 5" - 6" thick
3. Existing concrete cracked due to deep soft sand material
4. Thicker gravel base will minimize settling under new pavers

Sub Total	\$	1,684.75
Tax	\$	106.98
Total	\$	1,791.73

Item
3.0

Accent Border at Pool Deck Perimeter

Accent Border at Main Pool Deck Perimeter	\$	377.33
Accent Border at Walk Perimeter	\$	242.55
Accent Border at Add'l Pool Deck Perimeter	\$	201.17
Sub Total	\$	821.05
Tax	\$	52.14
Total	\$	873.18

Notes:

1. Accent pavers to be Parisien rectangle - Champlain Grey

Total Cost - Phase 1B - Add'l Work Order #1 \$ 6,456.97

*Prepared by Dane J. White, P.E.
Perfect Curb, LLC - Owner/Gen Mgr
CT License # - HIC.0636253
May 13, 2019*